

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Co. - (Mike Cherry)

Complete Address Box 987 - St. Bend, Kansas 67530

Lease Name Earl 'e' Well No. 7

Location NW - SW - NE Sec. 13 Twp. 10 Rge. 20 (East) (West)

County Rooks Total Depth 3749

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing

Address Hays, Kansas 67601 License No. _____

Operation Completed: Hour: 1:30pm Day: 10 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 258' w/175 sy. 5 1/2" @ 3748' w/150 sy
Open hole comp. 3746-49 - Squeezed @ 997' w/300 sy.
cont. w/1850# PSI - Squeezed @ 1200' in 1952 -
Ordered 250" sy 50% poz mix 69 gal 32 cc, 14 gal, 7 hulls & 5 1/2" plug.
Pumped in 5 1/2" 1 hull -> 50 cnt & 2 hulls -> 14 gal & 2 hulls -> 5 1/2" wiper
plug -> 85 cnt & 2 hulls - 400# P.S.I. shut in: Hook-up
to 8 5/8" pumped 90 sy cont. P.S.I. to 500# P.S.I. shut in

Amount of Surface Casing: 258'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
INVOICED
DATE 9-23-82
INV. NO. 1154-W

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1982
Conservation Division Agent
CONSERVATION DIVISION
Wichita, Kansas
09-14-82