

15-163-03532-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1978
09-25-78
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Sutor "A" Well No. 5

Location NE NE SE Sec. 13 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3763'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:10 P Day 20 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3763' 8 5/8 csg set 1624' cwc 800 sk.

5 1/2 csg set 3761' cw 150 sk cem.

Filled 5 1/2 csg W/sd to 3000' -dumped 5 sk cem. W/dump bailer. (3000'-2960')

Cutoff & recovered 2821' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water -released 8 5/8 plug & pumped 50 sk

50-50 poz 2% -displaced with 8 sk gel & water & capped with 25 sk 50-50 poz 2%

& shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-26-78

INV. NO. 8166-W

Signed: [Signature]
Well Plugging Supervisor