

15-163-03328-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE SE NW

SEC. 13 TWP. 10 RGE. 20

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease _____ Sutor _____

Operator Petroleum Inc Address Wichita, Kans

Field _____ County Hooks

Total Depth 3804 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 313' circulated with cement-5 1/2" at 3790' with
100 sax cement behind.

Filled hole with chat to 3500' and set 5 sax cement with
dump bailer, pulled 3100' 5 1/2", filled hole to 300' with
heavy mud, set bridge and 15 sax cement, filled with mud
to 35' set bridge and 10 sax cement to bottom cellar.

RECEIVED
Conservation Div.

JUL 18 1950 07-18-50

Edou
STATE CORPORATION
COMMISSION
District Conservation Agent

Date 7-14-50

PLUGGING
FILE SEC 13 T 10 R 20
BOOK PAGE 17 LINE 5