

15-163-20032-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-10-67
JUL 19 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address: P. O. Box 308 Ellinwood, Kansas

Lease Name Brueggeman Well No. 8

Location NW SW NE Sec. 15 Twp. 10 Rge. 20 (E) (W) X

County Rooks Total Depth 3835

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 4 P Day 6 Month 7 Year 1967

The Above well was plugged as follows:

RTD 3835' 8 5/8 csg set at 973' cwc 425 sc.
Gunned pits, Circulated heavy mud, set cementing plug at 950' and displaced 20 sc cem.
thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7-10-67

INV. NO. 5548-W