

15-163-02144-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1972
11-10-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address 2915 N. Lincoln Oklahoma City, Oklahoma 73105

Lease Name Brueggeman Well No. 4

Location C SE NE NW Sec. 15 Twp. 10Rge. (E) (W) 20

County Rooks Total Depth 3760'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools by HOWCO

Address _____ License No. _____

Operation Completed: Hour 5 P Day 6 Month 11 Year 1972

The above well was plugged as follows:

Total Depth 3760' 8 5/8 csg set at 181.55' cwc 125 sk.

5 1/2 csg set at 3754' cw 150 sk cmt.

5 1/2 csg squeezed at 1035' W/200 sk cmt.

Ran 119 jts tbgs set at 3630' - pumped 25 sk gel & water W/100 lbs hulls - displaced

25 sk cmt. Pulled 96 jts tbgs set at 700' -circulated 70 sk cmt to surface. Pulled

remaining 23 jts tbgs & capped 5 1/2 csg W/5 sk cmt.

Pumped 10 sk cmt down annulus.

I hereby certify that the above well was plugged as herein stated.

Signed: Lew J. Manning
Well Plugging Supervisor

INVOICED

DATE 11/10/72
INV. NO. 6613-11