

15-163-00652-0000

Form CP-3
Rev. 6-4-68

KANSAS

al
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Williams Well No. 1

Location NW NW NW Sec. 16 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3821'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 11 A Day 5 Month 5 Year 1973

The above well was plugged as follows:

Total Depth 3821' 8 5/8 csg set at 129' cwc

5 1/2 csg set at 3815' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3800-3521) dumped 5 sk cmt W/dump bailer. (3765-3800)

Dakato squeezed A/1000'.

Cutoff and recovered 780' of 5 1/2 csg.

Pumped down 8 5/8 vsg with 25 sk gel & water W/500 lbs hulls, released 8 5/8 plug

and pumped 120 sk 50-50 poz W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Geo. F. Mansour*
Well Plugging Supervisor

DATE 5-9-73

INV. NO. 7327-W