

15-163-00521-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-9

LOCATION SE SE SW

SEC. 10 TWP. 10 RGE. 20

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Shaw

Operator Sunray Oil Co Address Great Bend, Kans

Field _____ County Rooks

Total Depth 3800 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address Chase Kans

(Describe briefly the manner in which the well was plugged)

8 5/8" at 312' circulated with cement - 5 1/2" at 3735' with
75 sax cement behind.

Filled with sand to 3745' set 4 sax cement with dump bailer, pulled
3050' 5 1/2", mud to 312', set rock and 15 sax cement, mud to
35', set rock and 10 sax cement to bottom cellar.

10-20-53

District Conservation Agent

Date 10-18-53

PLUGGING
FILE SEC 16 T 10 R 20W
BOOK PAGE 121 LINE 9

CONSERVATION DIVISION
WICHITA, KANSAS