



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 9-9-1968
 SEP 9 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Chief Drlg. has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc.

Complete Address: Box 797 Great Bend, Ks.

Lease Name: Bowyer Well No. 1

Location: SW NW NE Sec. 4 Twp. 12 Rge. 18 (E)(W)X

County: Ellis Total Depth 3360' Oil Well

Gas Well Input Well AWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug, at 660' and displace

70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Geo F. Massey
 Conservation Division Agent