

State of Kansas



15-051-20045-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
4-18-1967  
APR 18 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Davenport of Sage Drilling Co. Inc. has this  
date requested permission to plug the following described well:

Mr. Davenport guarantees payment of the plugging fee.

Operator's full Name: J. A. Allison ETAL

Complete Address: 1415 Wichita Plaza Bldg. Wichita, Kansas

Lease Name: Mc Intosh Well No. 1

Location: NE SE SW Sec. 6 Twp. 12 Rge. 18 (E)(W) X

County Ellis Total Depth 3514' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Davenport was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 550' and displace  
20 sc cement thru drill pipe, Heavy mud to 200' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug  
1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc  
cement.

Very truly yours,

Geo. J. Messing  
Conservation Division Agent