

State of Kansas



15-051-20015-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
Z-28-1967
FEB 28 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Flake of Woodman-Iannitti Drlg. has this

date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman-Iannitti Drlg. Co.

Complete Address: 706 Union Nat'l Bldg. Wichita, Kansas

Lease Name: Stackhouse Well No. 2

Location: C S/2 SE NW Sec. 7 Twp. 12 Rge. 18 (E)(W) X

County Ellis Total Depth 3620' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace
20 sc cement thru drill pipe. Heavy mud to 170' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent