

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling & Sons has this

date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation

Complete Address: 1000 Century Plaza Wichita, Ks.

Lease Name: Thomas Well No. 1

Location: SE NW SW Sec. 21 Twp. 10 Rge. (E)(W) 20

County: Rooks Total Depth 3475' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and ~~displace~~

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Messerly
Conservation Division Agent