



15-051-22850-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Wilber Cotton of Big Springs Drilling, Inc has this date requested permission to plug the following described well:

Operator's Full Name: Green Oil Operation

Complete Address: P.O. Box 503, Hays, Ks. 67601

Lease Name: General Seitz "A" Well No. 1

Location: SE NW NE Sec. 4 Twp. 12 Rge. 19 (E) (W)

County: Ellis Total Depth: 3700'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Cotton was instructed to plug the well as follows:

8 5/8"-246' S.P. cuc. W/ 165 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot W/ drill stem W/ heavy mud between all plugs.

1st plug @ 780' W/ 70 sacks cement

2nd plug @ 250' W/ 40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' W/ 10 sacks cement

Circulate 10 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1967
3-8-1967
CONSERVATION DIVISION
Wichita Kansas

Very truly yours,

[Signature]
Conservation Division Agent