

State of Kansas



15-051-20386-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-5-1969
FEB 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger Drlg. has this date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: A. Ainsworth

Complete Address: 222 Brown Bldg., Wichita, Kansas

Lease Name: Evans Well No. 1

Location: SW NW SW Sec. 20 Twp. 12 Rge. 18 (E)(W) XX

County: Ellis Total Depth 3773 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Fickle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cement to base of cellar. Plug rat hole
with 2 sk cement.

Very truly yours,

Ken J. Massey
Conservation Division Agent