

15-163-03334-0000

County. Sec. 16 Twp. 10S Rge. 20 ~~XOFX~~ (W)

Lease Owner Heathman Drilling Co., Inc., et al

Lease Name SHAW Well No. 1

Office Address.....509 Orpheum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed.....5-29-1950.....

Application for plugging filed.....(verbal).....5-29-1950.....

Application for plugging approved.....(written) 5-31- 1950

Plugging commenced 5-29- 1950

Plugging completed.....5-29-1950

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was com-

.....
 menced?.....yes.....

d plugging of this well.....Eldon Petty, Hays, Kansas

..... Depth to top..... Bottom..... Total Depth of Well.....3839.....Feet

and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with heavy mud to 130'; set plug and cemented to top w/40 sacks cement; cut pipe off 3' below ground level.

RECEIVED

JUN 6 X 1950

06-06-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Heathman Drilling Co., Inc.
Address.....509 Orpheum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert F. Walters (employee of owner) ~~owner of operation~~ of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Waller

509 Orpheum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of June, 1950

My commission expires June 28, 1952

22-7377-S 4-49-10M

22-1811-8

PLUGGING

FILE SEC 16 T 10 R 20

BOOK PAGE 8 LINE 39

SHAW # 1 WELL

Location:	C. East Line SE/4 SE/4 Sec.16-10S-20W Rooks County, Kansas	Date Spudded:	5-21-50
Operator:	Heathman Drilling Co., Inc.	Date Rotary Compl:	5-29-50
Contractor:	Heathman Drilling Co., Inc.	Elevation:	2183 DF; 2181 Gr; 2185 KB
Surface Casing:	8-5/8" (4 jts.) 135' overall set @ 132' w/80 sacks and 1 CC	Rotary Total Depth:	3839'
Oil String:	Nonerun Dry and ABANDONED 5-29-50		

T O P S KB

Anhydrite	1676 (+ 509)
Topeka	3220 (-1035)
Heebner	3430 (-1245)
Lansing-K.C.	3470 (-1285)
Base of K.C.	3698 (-1513)
Shale Conglomerate	3732 (-1547)
"Sink Hole Clays"	3746 (-1561)
Total Depth	3839 (-1654 in clay)

(Chert Conglomerate not reached.)

L O G

(Figures indicate bottom of formation)

Shale and sand	0 to 135
Shale	380
Shale	760
Sand shale	1420
Shale	1676
Anhydrite	1708
Shale and shells	1840
Shale and shells	2270
Shale and lime	3385
Lime	3797
Conglomerate	3839
Total Depth	3839'

DST 3502 to 3531' - 29' anchor -
 packer open 15 min.
 " closed 10 min.
 Recovered 180' salt water
 Bottom hole pressure
 1070#.

The undersigned, H. D. Shreve, Heathman Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in the drilling of the above well as reflected by the Daily Drilling Reports.

HEATHMAN DRILLING CO., INC.


BY:

Robert F. Walters
 Robert F. Walters

Subscribed and sworn to before
 me this 2nd day of June, 1950.

D. Marionie Mott
 Notary Public

My commission expires: June 28, 1952.



COMMISSION
 KANSAS