


15-163-00652-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County, Sec. 16 Twp. 10 Rge. 20 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Okmar Oil Co.
Lease Name Williams Well No. #1
Office Address 1130 Vickers KSB&T Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 3-5-73 19
Application for plugging approved 19
Plugging commenced 4-30-73 19
Plugging completed 5-5-73 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3815' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3815'	786.66'
				8 5/8"	129'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3800'. Mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 25 sacks gel - 5 sacks hulls and 120 sacks posmix with 6% gel.


RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Southwest Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

Subscribed and Sworn to before me this 7 day of May, 1973
Sidney D. Miller
Notary Public.



15-163-00652-0000

DRILLING REPORT

NE/4 NW/4 NE/4 Sec. 16-100-20W
Rooks County, Kansas

Date Spudded: 3-25-50

Operator: Heathman Drilling Co., Inc.

Rotary Completed: 4-4-50

Contractor: Heathman Drilling Co., Inc.

Total Depth: 3815'

Surface Casing: 4 jts. (129') 3-5/8" cemented
w/100 sacks, and 1 sack Cal.
Colorado @ 129'.

Elevation: 2241 Cr.
2244 BF
2246 KB

Oil String: 122 jts. (3685') 5-1/2" 11/8" 8 thd.
cemented w/100 sacks @ 3815' T.D.

LOG

Anhydrite	1732 (+ 514)
Topoka	3200 (-1034)
Keokuk	3485 (-1239)
Leaning-K.G.	3520 (-1202)
Base K.G.	3750 (-1504)
Conglomerate	3786 (-1510)
Sisgum	3798 (-1502)
Arbuckle	3813 (-1507)
Rotary Total Depth	3815

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1971
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1973
CONSERVATION DIVISION
Wichita, Kansas

LOG
(Figures indicate bottom of formation)

Sand and shells	0 to	130
Shale and shells		320
Shale		920
Sand and shale		1028
Shale		1205
Sand		1445
Shale and shells		1600
Shale, Red Bed		1732
Anhydrite		1755
Shale, shells		1870
Shale		2114
Shale and shells		2295
Shale, lime		3255
Shale		3260
Lime		3406
Lime and shale		3541
Lime		3785
Conglomerate		3803
Sandy shale		3813
Lime		3815
Total depth		3815'

DRILLING-IN INFORMATION

4-7-50 P.M. - Drilled plug - - rainbow showoil
DD to 3817 1/2 - no increase.

4-8-50 - - - DD to 3819 - 1/2 boph
DD to 3821 - 400' oil - 1 hr.
1000' oil - end of 2
hour.

Swabbed 5 boph - 400' OB - 12 hr
Acid - 500 gal. - swb. 15 boph -
1400' off bottom - 2 hr

Running tubing and rods.

The undersigned, Heathman Drilling Co., Inc., hereby certifies that the above log
is a true and correct log of the formations encountered in drilling the above noted
well as reflected by the Daily Drilling Reports.

HEATHMAN DRILLING CO., INC.

By: Robert F. Walters
Robert F. Walters

Subscribed and sworn to before
me this 7th day of April, 1950.

D. Marjorie Mott
Notary Public

My commission expires: June 28, 1952.