

15-163-00521-000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 16 Twp. 10S Rge. 20 (W)

Location as "NE/CNW/SW" or footage from lines C-SE-SE-SW

Lease Owner Sunray Oil Corporation

Lease Name Shaw Well No. 1

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 6 19 53

Application for plugging filed August 11 19 53

Application for plugging approved August 12 19 53

Plugging commenced October 6 19 53

Plugging completed October 18 19 53

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation none Depth to top Bottom Total Depth of Well 3800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3451		8 5/8	312	none
Lansing-KC	water	3490	3593	5 1/2	3755	3080
Simpson		3746				
Arbuckle	water	3753	3800			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3800' to 3745' and ran 4 sax cement. Pulled 3080' of 5 1/2" casing. Mudded hole to 312' and set 10' rock bridge and 15 sax cement. Mudded hole to 35' and ran 10 sax cement to surface. Hole plugged under the supervision of Eldon Petty, Corporation Commission Representative.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton

Robert K. Crouch (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch


Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 19 53

Notary Public

My commission expires December 24, 1956

24-2675-5 2-52-20M



00123 1953

15-163-00521-0000

DRILLER'S LOG

Sunray Oil Corporation
#1 N. F. Shaw
SE SE SW - 16-10S-20W
Rooks County, Kansas

<u>FROM</u>	<u>TO</u>	
0	40	Sand
40	80	Sand & shale
80	316	Shale & shells
0	315	Reaming
315	775	Shale & shells
775	930	Sand
930	1300	Sand & shale
1300	1490	Shale & red bed
1490	1685	Shale & shells
1685	1730	Anhydrite
1730	2150	Shale & shells
2150	3367	Lime & shale
3367	3696	Lime
3696	3761	Lime & shale
	3761	ROTARY TOTAL DEPTH

COMMENCED: 7-16-53
COMPLETED: 7-28-53

CASING RECORD

Set 8-5/8" surface casing at 312' with 225 sacks cement.
Set 5-1/2" casing at 3755' with 75 sacks cement.


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 N. F. Shaw located SE SE SW of Section 16-10S-20W, Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY

BY: *Leon L. Mehler*
Leon L. Mehler

Subscribed and sworn to before me this 30th day of July, 1953.



Jacqueline Korman
Notary Public

My Commission Expires: May 2, 1956

PLUGGING
FILE SEC 16 T 20 R 20w
BOOK PAGE 121 LINE 9

JUL 28 1953
CONSERVATION