

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-00632-0000
API NUMBER Spud 3/14/53

LEASE NAME Williams

WELL NUMBER #2

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 16 TWP. 10 RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 3/24/53

Plugging Commenced 11:30 A.M. 4/20/93

Plugging Completed 12:30 P.M. 4/20/93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 20, 1993 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top Bottom T.D. 3707

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	166'	None
				5 1/2"	3705'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Down 5 1/2" casing, mixed 5 sx hulls with 290 sx cement. Max press. 1000#.
Shut in 900#. Pressured 8 5/8" casing to 500#. Held O.K.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., License No.

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales (Employee of Operator) or

above-described well, being first July sworn on oath, says: That I have knowledge of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 21 day of April, 1993

BETTY JANE BITTEL
State of Kansas
My Appt. Exp. July 17, 1996

Betty Jane Bittel
Notary Public Betty Jane Bittel

My Commission Expires: July 17, 1996.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1993

CONSERVATION DIVISION
Wichita, Kansas

15-163-00632-0000

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN FARM NAME WILLIAMS NO. 2
 LOCATION NW SE NE SEC. 16-10S-20W
 POOL NAME _____ COUNTY ROOKS STATE KANSAS
 COMMENCEMENT DATE March 14, 1953 COMPLETION DATE March 23, 1953

LOG OF WELL

Elevation: 2156' R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	166	Sand-Shale		
166	400	Sand-Shale		
400	715	Sand-Shale		
715	765	Sand		
765	1115	Shale-Sand		
1115	1330	Sand		
1330	1400	Red Bed		
1400	1612	Red Bed	0° - 1500'	
1612	1655	Anhydrite		
1655	1800	Shale		
1800	2125	Shale	0° - 2000'	
2125	2285	Lime-Shale		
2285	2450	Lime-Shale		
2450	2560	Lime-Shale	0° - 2500'	
2560	2660	Lime-Shale		
2660	2800	Lime-Shale		
2800	2900	Lime-Shale		
2900	2995	Lime-Shale		
2995	3085	Lime-Shale	0° - 3000'	
3085	3170	Lime-Shale		
3170	3240	Lime-Shale		
3240	3305	Lime-Shale		
3305	3335	Lime-Shale		
3335	3405	Lime-Shale		
3405	3450	Lime-Shale		
3450	3490	Lime		
3490	3535	Lime	0° - 3500'	
3535	3580	Lime		
3580	3630	Lime		
3630	3665	Lime-Shale		
3665	3707	Lime-Shale		

RECEIVED
 MAR 29 1953
 D. G. Hansen, Contractor
 By _____

CASING LEFT IN HOLE AFTER COMPLETION

Ran 166.01 (5 jts) 8 5/8" OD 24# casing.
 Set 3725.93' of 5 1/2" OD 14# casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Vicky Jacobs

Subscribed and sworn to before me this 25th day of March, 1953.

My commission expires: 11/21/55

Marjorie Schmidt
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 APR 26 1953
 CONSERVATION DIVISION
 d. Kansas