

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-20,620-0001

06-11-98

LEASE NAME Keller "P"

TYPE OR PRINT

WELL NUMBER 5

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days. 6-11-98

660 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.

SEC. 21 TWP. 10 RGE. 20 (E) or (W)

ADDRESS P.O. Box 783188 Wichita, KS 67278-3188

COUNTY Rooks

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Date Well Completed 5/76

Character of Well oil

Plugging Commenced 6/4/98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/4/98

The plugging proposal was approved on June 4, 1998 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3760

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	289	n/a
				4 1/2"	3752	n/a

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Tubing at 1878' cemented w/35 sx 60/40 Poz, 10% gel followed w/40 sx 60/40 Poz, 10% gel & 100# hulls. Tubing at 1108' cemented to surface w/25 sx 60/40 Poz & 100# hulls. Swaged onto 4 1/2" casing & squeezed w/25 sx 60/40 Poz & 50# hulls. Max press. 1000#, stp 800#. Plgd annulus w/50 sx 60/40 Poz & 50# hulls. Max  
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) \_\_\_\_\_



AND SWORN TO before me this 10th day of June, 19 98

[Signature]  
Julie K. Stout Notary Public

My Commission Expires: July 23, 2001

pressure 600#, SIP 500#. Plugged down at 3:15 p.m. 6-4-98.