

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County, Sec. 21 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 SW/4

Lease Owner Heathman-Seeligson Drilling Co.

Lease Name JOHN KELLER Well No. 2

Office Address 254 No. Washington, Wichita 7, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 12-14-1953

Application for plugging filed 12-14-1953

Application for plugging approved 12-14-1953

Plugging commenced 12-14-1953

Plugging completed 12-14-1953

Reason for abandonment of well or producing formation -- dry hole --

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation -- Depth to top - Bottom - Total Depth of Well 3835 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|---------|-------------------------|------------|
| none | - | - | - | 8-5/8 " | 168.51 | none |
| | | | | | cemented with 105 sacks | |
| | | | | | cement and 1 sack Cal. | |
| | | | | | Chloride. | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud; set bottom plug @ 160' w/15 sacks cement; top plug @ 40' w/10 sacks cement and 1 sack hulls.

12-19-53

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Heathman & Seeligson Drilling Co.
Address 254 No. Washington, Wichita 7, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. H.D. Shreve (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HEATHMAN SEELIGSON DRILLING CO.

(Signature) By: [Signature]
254 No. Washington, Wichita 7, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of December, 1953

My commission expires June 28, 1956 D. Marjorie Mott Notary Public.



DRILLERS' LOG

Name: #2 JOHN KELLER Elevation: 2193 Gr
 2196 Df
 2199 KB
 Location: SW/4 SE/4 SW/4 Sec. 21-10S-20W
 Rocks County, Kansas
 Operator: Heathman-Seeligson Drilling Co. Commenced: 11-30-53
 Contractor: Heathman-Seeligson Drilling Co. Completed: 12-14-53
 Casing: 8-5/8" surface casing cemented
 @ 168.51 ft. w/105 sacks Victor
 cement and 1 sack Cal. Chloride.
 Plug down 6:30 PM 11-30-53
 Rotary T.D.: 3835'
 D & A - no oil string run.

GEOLOGICAL TOPS (KB)

| | |
|-----------------------------|--------------|
| Anhydrite | 1673 (+ 526) |
| Topeka | 3246 (-1147) |
| Heebner | 3455 (-1256) |
| Toronto | 3477 (-1278) |
| Lansing-K.C. | 3495 (-1296) |
| Six Conglomerate | 3760 (-1561) |
| Total Depth | 3835 (-1636) |

LOG

(Figures indicate bottom of formation.)

| | |
|---------------------------|---------|
| Clay and sand | 0 to 75 |
| Blue shale | 175 |
| Shale and shells | 795 |
| Shale, shells and red bed | 920 |
| Shale, shells and sand | 1485 |
| Red Bed | 1673 |
| Anhydrite | 1715 |
| Shale and shells | 2400 |
| Shale and lime | 2565 |
| Shale and shells | 2800 |
| Lime and shale | 2885 |
| Lime | 2940 |
| Lime and shale | 3185 |
| Shale | 3315 |
| Lime | 3465 |
| Shale and lime | 3510 |
| Lime | 3716 |
| Lime and shale | 3760 |
| Conglomerate | 3835 |
| Total Depth | 3835 |

The undersigned, H. D. Shreve, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-SEELIGSON DRILLING CO.

By H. D. Shreve

Subscribed and sworn to before me
this 18th day of December 1953.

D. Marjorie Matt
Notary Public

My commission expires: June 28, 1956



PLUGGING
 FILE SEC 21 T 10 R 20W
 BOOK PAGE 149 LINE 41