

15-163-00870-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS County. Sec 21 Twp. 10 Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW SW  
Lease Owner C-G DRILLING CO. & D. G. HANSEN  
Lease Name JOHN KELLER Well No. }  
Office Address 107 RULE BLDG., WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed December 4 1955  
Application for plugging filed December 4 1955  
Application for plugging approved December 4 1955  
Plugging commenced December 5 1955  
Plugging completed December 5 1955  
Reason for abandonment of well or producing formation Too low structurally

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty, Mays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3822 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	193'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 188'. Set plug. Put in 1/2 sack Hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug Filled to top with 1/2 sack Hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor C-G DRILLING CO.  
Address 107 RULE BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
107 Rule Bldg.  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1955

My commission expires 5-20-59



Vicky Jacobs  
Notary Public.

12-10-55

PLUGGING  
FILE SEC 21 T 10 R 20 W  
BOOK PAGE 22 LINE 4

15-163-00870-0000

CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. & D. G. HANSEN WELL NAME JOHN KELLER #1

LOCATION SE SW SW Sec. 21-10-20 RIG #1

COUNTY \_\_\_\_\_ ROOKS STATE KANSAS

COMMENCEMENT DATE NOVEMBER 26, 1955 COMPLETION DATE DECEMBER 5, 1955

LOG OF WELL

Elevation 2211' rotary bushing.

All measurements taken from the top of rotary bushing

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	193	Shale		
193	860	Shale		
860	940	Sand		
940	1050	Shale		
1050	1125	Shale		
1125	1420	Sand		
1420	1676	Red Bed		
1676	1716	Anhydrite		
1716	1750	Shale-Shells		
1750	2175	Shale-Shells		
2175	2365	Lime-Shale		
2365	2510	Lime-Shale	0° - 2500'	
2510	2640	Lime-Shale		
2640	2850	Lime-Shale	0° - 2750'	
2850	2955	Lime-Shale		
2955	3105	Lime-Shale	0° - 3000'	
3105	3260	Lime-Shale	0° - 3250'	
3260	3404	Lime-Shale		
3404	3510	Lime-Shale	0° - 3500'	
3510	3600	Lime-Shale		
3600	3680	Lime-Shale		
3680	3735	Lime-Shale		
3735	3801	Lime-Shale	0° - 3750'	DST 3797 - 3801
3801	3822	Lime-Shale		DST 3801 - 3807
	3822	TD		

CASING LEFT IN HOLE AFTER COMPLETION

193' of 8-5/8" OD Surface Casing

STATE OF KANSAS, COUNTY OF SEDGWICK ) ss.

THE undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
G. F. Galloway

Subscribed and sworn to before me this 8th day of December, 1955.

My commission expires;  
May 20, 1959

Vicky Jacobs  
Vicky Jacobs, Notary Public

**PLUGGING**  
FILE SEC 21 T 10 R 20W  
BOOK PAGE 22 LINE 4