

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
Address: 100 S. Main, Suite 200, Wichita, KS 67202
Phone: (316) 262-3596 Operator License #: 9408
Type of Well: Injection Docket #: E-19,049
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 8/12/09 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-21,008-00-01
Lease Name: Popp
Well Number: #1
Spot Location (QQQQ): SW - SE - SE -
330' Feet from North / South Section Line
660' Feet from East / West Section Line
Sec. 4 Twp. 16 S. R. 14 East West
County: Barton
Date Well Completed: _____
Plugging Commenced: 8/10/09
Plugging Completed: 8/12/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	293'	
				4-1/2"	3480'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

(SEE ATTACHED REPORT)

Name of Plugging Contractor: Klima Well Service, Inc. License #: 7023
Address: P.O. Box 386, Claflin, KS 67525-0386
Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation
State of Sedgwick County, Kansas, ss.
Gary Sharp

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Gary Sharp

(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 24th day of August 2009

Glenna E. Lowe
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Trans Pacific Oil - Daily Drilling or Workover Report

Popp 1

Well	Popp 1	STR	3&4-16S-14W	City	Barton	State	Kansas
GL:	KB:	Location	SW(3)SE(4)				

Surf Csg 8 5/8" @ 293' w/ 175 sx

Prod Csg 4 1/2" @ 3480' w/ 125 sx

Perfs 3299-3303, 3313-18, 3339-41,3379-88

Date Report

- 8/3/2009 Klima Well Service MIRU to pull and plug. Found tbg stuck tried to back off and parted 2 3/8" tbg at 476 ft. RD
- 8/10/2009 Klima Well Service MIRU to pull parted tbg. RIH with 5 jts wash over pipe with mill shoe, washed down 163 ft. while circ. COH. RIH with overshot and fished, was able to release packer pulled 4 jts. SD.
- 8/11/2009 pulled remaining 98 jts. Of junk tbg. And Arrow packer SD.
- 8/12/2009 Perf Tech, perforated @ 950,450,150 was unable to shot at 1500. RIH with 96 jts. Rented 2 3/8" tbg. To 3000 ft. Quality Cementing plugged with 9 sx gel and 50 sx 60/40 poz mix 4% gel and 100#s hulls. Pulled to 1550 pumped 100 sx and 200#s hulls, pulled to 475 pumped 55 sx circ. Out 4 1/2" casing shut valve, pumped 35 sx to fill 8 5/8. Pulled last 16 jts topped off with 5 sx. RDMO Well was plugged to KCC req. Bruce Rodie KCC rep.

Perf Tech tkt. # 6604

Quality Cementing tkt. #3328

RECEIVED
AUG 26 2009
KCC WICHITA