

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32659
Name: Phoenix PetroCorp, Inc.
Address 1: 6401 S. Custer Rd. Ste 130
Address 2: _____
City: McKinney State: TX Zip: 75070 + _____
Contact Person: George Tarbox
Phone: (469) 452-6031
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 4658' Bottom: 4680' T.D. 5001'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 129-207²33 - 00 00 KCC PKA
Spot Description: _____
C - SW SW Sec. 18 Twp. 35 S. R. 41 East West
660 Feet from North / South Line of Section
4,620 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW KCC papers 8/2/09
County: Morton
Lease Name: Northwest Flats Unit Well #: 3-2
Date Well Completed: 10/4/1980
The plugging proposal was approved on: _____ (Date)
by: Lyn Reimer (KCC District Agent's Name)
Plugging Commenced: 8/19/2009
Plugging Completed: 8/24/2009

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|---------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | Surface | 10 3/4" | 1330' | None |
| | | Production | 7" | 5001' | 1360' |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 7" cement retainer at 3667', just above ESP fish. Squeeze thru retainer w/100 sks class "C" cement and dump 10 sks on top, est TOC @ 3600'. Circulated hole w/mud. Cut casing @ 2589', 1595' and 1360'. Pull csg from 1360'. Run tbg @ 1360' & spot 75 sks class "C" cement up to 1175'. WOC. Tag TOC @ 1142'. Pull tbg up to 400' spot 60 sks class "C" cement up to 253'. Top out 40'-4' with 25 sks class "C" cement. Cut off below plow depth.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc
Address 1: PO Box 1706 Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: Phoenix PetroCorp, Inc.
State of Kansas County, Morton, ss.
George Tarbox Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] 8-28-09

KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 02 2009
RECEIVED