

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25109-00-01
Spot: SWNWNW Sec/Twnshp/Rge: 1-19S-15W
990 feet from N Section Line, 330 feet from W Section Line
Lease Name: WIEDEMANN Well #: 6
County: BARTON Total Vertical Depth: 3690 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	946	0	w/350 sxs cmt
PROD	5.5	3689	0	w/165 sxs cmt

11993

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2009 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D.DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2009 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Cut casing at 1405'.
Tied to casing and pumped 150 sxs cement with 200# hulls.
Pulled to 550' - tied to casing and pumped 150 sxs cement with 300# hulls.
Pulled casing and topped off with 10 sxs cement.

INVOICED
DATE 11-10-09
INV. NO. 2010060475

RECEIVED
SEP 25 2009
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #C32929.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

Form CP-2/3

SEP 23 2009

LD DRILLING
GREAT BEND KS67530

#6 WIEDEMANN OWWO

1-19S-15W
SW NW NW
KANSAS

City: BARTON

Spot: C SW NW NW API 15-009-25109

Site: 1-1/4 S & 3-3/4 E OF ALBERT KS

Lat/Long: 38.43169 -98.93977

Field: OTIS-ALBERT

P&A

FR: 01/01/2009 Spd: 01/05/2009 Drg Cp: 01/05/2009 Issued: 02/23/2009 Revised: 02/23/2009

Copyright 2009 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

RTD OLD 3690 -1704

P&A, REAGAN, 1/16/2009

LTD OLD 3692 -1706

Notes: CORRECTION 3/14/2008 - ORIG FR AS LD

DRILLING AS CONTR

Contr: UNKNOWN

Geol: NONE

Elev: 1986 KB, 1981 GL, 1984 DF

Information Tops: (L-Log, S-Sample, D-Driller)

L ANH	960 +1026
S B/ANH	985 +1001
L CHASE	1842 +144
L WINF	1892 +94
L TOP	2977 -991
L HEEB	3217 -1231
L BR LM	3297 -1311
L LANS	3305 -1319
L BKC	3520 -1534
L ARB	3586 -1600
L REAGAN SD	3631 -1645

Old Info:

Well Record: LD DRILLING, #6 WIEDEMANN, SPD 03/15/2008, DC 03/21/2008, 8-5/8" 946 / 350 SX (ALT 1), 5-1/2" 3689 / 165 SX, OIL, P 1 BO & 200 BWP, ARB 3586-3592, REAGAN 3631-3634, 4/8/2008(CARD ISSUED 05/12/2008)

Contr: PETROMARK DRILLING #2

Geol: KIM B. SHOEMAKER

Find:

COMMENT: PROPOSED START 12/3/2007; MI & RURT 3/14/2008; S.D. RIG SVC UNTIL 3/15/2008
NO CORES

LD DRILLING
GREAT BEND KS67530

#6 WIEDEMANN OWWO

1-19S-15W
SW NW NW
KANSAS

Copyright 2009 Independent Oil & Gas Service, Inc. Wichita, KS

Side 2

DST(1) 3506-3597 (ARB) 30-45-45-60, WB BLT TO 4 INCH/30", ISI: NB, (2ND OP) WB BLT TO 4 INCH/45", FSI: NB, REC 120' OIL & GCM (5% G, 15% OIL, 80% M) ISIP 338# FSIP 311# IFP 107#-115# / FFP 118#-124# IHP 1768# FHP 1732# BHT 116"

DST(2) 3595-3604 (ARB) 30-45-45-60, (1ST OP) WK SURF BLO BLT TO 1/2 INCH IN BKT, ISI: NB, (2ND OP) NB, FSI: NB, REC 25' M, NS ISIP 901# FSIP 1523# IFP 61#-67# / FFP 64#-65# IHP 1765# FHP 1744# BHT 115"

DST(3) 3601-3613 (ARB) 30-45-45-60, (1ST OP) WB BLT TO 1 INCH IN BKT, ISI: NB, (2ND OP) NB, FSI: NB, REC 20' M, NS ISIP 650# FSIP 583# IFP 39#-41# / FFP 42#-51# IHP 1783# FHP 1753# BHT 111"

DST(4) 3611-3626 (ARB) 30-45-45-60, (1ST OP) WK INTRMNT BLO BLT TO 1 INCH IN BKT, ISI: NB, (2ND OP) NB, FSI: NB, REC 25' V SLI OCV (1% OIL, 99% W) ISIP 1127# FSIP 1096# IFP 42#-52# / FFP 48#-57# IHP 1791# FHP 1765# BHT 114"

DST(5) 3620-3635 (ARB, REAGAN SD) 30-45-45-60, (1ST OP) WB BLT TO 3 INCH IN BKT, ISI: NB, (2ND OP) WB BLT TO 9 INCH IN BKT, FSI: BLO BK, 90' GIP, REC 150' TF: 30' VHO & GCM (10% G, 40% OIL, 50% M), 60' SLI OIL & GCWM (5% G, 5% OIL, 80% M, 10% W), 60' V SLI OCMW (1% OIL, 39% M, 60% W) ISIP 1141# FSIP 1110# IFP 39#-75# / FFP 90#-102# IHP 1881# FHP 1771# BHT 116"

Comp Info: TRGT ZN: ARB (OIL), PTD 3650 (ARB), MICT (3/31/2008) - CO, PF (ARB) 3588-3592, (REAGAN SD) 3631-3634, W / 2 SPF, AC BOTH ZNS TOGETHER W/300 GAL (15% NE), SWB LD, SO, RE-AC 250 GAL (15% NE), SWB LD, SO, RE-AC 250 GAL (28% NE), SWB LD, SO, SET 2-7/8" TBG AT 3686, NO PKR, POP, IPP 1 BOPD & 200 BWP, DOFP 4/8/2008, COMMINGLED

New Info:

Well Record: FR 01/01/2009, REWORKED 01/05/2009, DC 01/05/2009

Find:

COMMENT: KCC API 15-009-25109-0001
Comp Info: MICT - CO, PF (LKC) 3306-3310,

(continued)

1-19S-15W
SW NW NW
KANSAS
Side 3

#6 WIEDEMANN OWWO

Copyright 2009 Independent Oil & Gas Service, Inc. Wichita, KS

LD DRILLING
GREAT BEND KS67530

3332-3340, ACD, NON-PROD, PF (CHER)
1846-1856, 1864-1874, 1892-1896, 1925-1987,
ACD, NON-PROD, SI - EVAL, DECISION MADE
TOP & A 1/16/2009 - NO OTHER INFO
AVAILABLE