

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21001-00-00  
Spot: W2NENW Sec/Twnshp/Rge: 34-20S-22W  
660 feet from N Section Line, 1830 feet from W Section Line  
Lease Name: MCFADDEN Well #: 3  
County: NESS Total Vertical Depth: 4330 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	417		WITH 250 SX CMT
PROD	5.5	4323	0	WITH 275 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/17/2009 6:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 40 SX CMT & 150# HULLS. PULL TBG TO 1400' & SPOT A HOT PLUG. PULL TBG TO 1000' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.  

140.73

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/17/2009 8:30 PM KCC Agent: MICHAEL MAIER

**Actual Plugging Report:**

1ST PLUG RAN BOND LOG FROM 1200' TO 80'. GOOD CMT. RAN TBG TO 4300' & PUMPED 40 SX CMT & 150# HULLS. 2ND PLUG PULLED TBG TO 1450' & PUMPED 50 SX CMT W/3% CC. 3RD PLUG PULLED TBG TO 970'. WAIT ON CMT 1 HOUR THEN CIRCULATED 125 SX CMT. PULLED TOH AND TOPPED WITH 10 SX CMT. 4TH PLUG PRESSURE 8 5/8" X 5 1/2" ANNULUS TO 500#.

**Perfs:**

Top	Bot	Thru	Comments
4323	4330		OH

INVOICED  
DATE 10-27-09  
INV. NO. 2010060424

RECEIVED  
OCT 01 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL & COMMON CMT W/3% BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED  
SEP 25 2009  
KCC DODGE CITY

Signed Michael Maier  
(TECHNICIAN)