

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23616-00-01
Spot: SENWSWSE Sec/Twnshp/Rge: 13-32S-4E
748 feet from S Section Line, 2236 feet from E Section Line
Lease Name: ROWE Well #: 3-13
County: COWLEY Total Vertical Depth: 3050 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	2410		
SURF	8.625	326		200 SX
PROD	5.5	3049	980	230 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2009 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT WELL PLUGGING Phone: (580) 763-7740

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS

99.13

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 09/02/2009 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/WIRELINE & SET CIBP @ 990', CUT CASING @ 980', LAYED DOWN 5-1/2" CASING. RIH W/TBG @ 980' CONSOLIDATED MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL. PULLED TBG @ 375', CONSOLIDATED MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 9-2-2009, 11:00 A.M.

Perfs:

Top	Bot	Thru	Comments
3012	3018		4 PER FOOT
3000	3002		
2330	2349		4 PER FOOT

INVOICED
DATE 10-27-09
INV. NO. 2010060425

RECEIVED
SEP 29 2009
KCC WICHITA

Remarks: CONSOLIDATED CEMENT TICKET #23062. GPS: LAT: 37.26116 LONG: -96.94098

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)