

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20243-00-02  
Spot: NESENE Sec/Twnshp/Rge: 3-4S-19W  
3630 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BECKMAN B Well #: 3  
County: PHILLIPS Total Vertical Depth: 3428 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227	0	175 SX
PROD	4.5	3409	0	200 SX

Well Type: EOR UIC Docket No: E20066.2 Date/Time to Plug: 09/24/2009 4:00 PM  
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION  
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Perforated at 1500' - 890' - 280'.  
Tubing and Packer stuck in the hole at 2550'.

111.41

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/24/2009 7:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2400' - pumped 75 sxs 60/40 pozmix - 4% gel with 100# hulls.  
Pulled tubing to 1200' - pumped 80 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled all tubing. Topped off 4 1/2" casing with 45 sxs 60/40 pozmix - 4% gel.  
Hooked onto 4 1/2" casing with swedge.  
Max. P.S.I. 200#. S.I.P. 175#.  
Check backside visually - full of cement.

Perfs:

Top	Bot	Thru	Comments
3233	3280		

INVOICED  
DATE 10/27/09  
INV. NO. 2010060426

RECEIVED  
OCT 02 2009  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #43722.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

CENTURY OIL OF KANSAS, INC.  
BOX 295, LOGAN, KS. 67646

#3 BECKMAN

3-4-19W  
NE SE NE

CONTR LAWBANCO DRLG. CTY PHILLIPS

GEOL KENNETH VEHIGE FIELD BECKMAN

E 2030 KB CM 8/15/78 CARD ISSUED 1/19/79 IP P 10 BOPD + 10 BWPD  
LKC 3233-80 OA

+	+	+
+	+	+
+	+	+

API 15-147-20,243

LOG	TOPS	DEPTH	DATUM
ANH		1533	+ 497
B ANH		1568	+ 462
TOP		2952	- 922
HEEB		3153	-1123
TOR		3182	-1152
LANS		3195	-1165
RTD		3410	-1380

8-5/8" 227/175sx, 4 1/2" 3409  
NO DST'S  
MICT - CO PF (LKC) 3276-80, 3233-37  
AC 9000, SWB LD + GSO, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS