

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21156-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 30-10S-19W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KELLER C (SE) OWWO Well #: 1
County: ROOKS Total Vertical Depth: 3668 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256	0	w/170 sxs cmt
PROD	4.5	3780	0	w/250 sxs cmt

119.21

Well Type: OIL/DH KCCPRT UIC Docket No: _____ Date/Time to Plug: 09/24/2009 9:30 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-7202

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 200# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2009 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3598' - pumped 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 2428' - pumped 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1218' - pumped 75 sxs 60/40 pozmix - 4% gel with 100# hulls to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.

Perfs:

INVOICED
DATE 10-27-09
INV. NO. 2010060427

RECEIVED
OCT 02 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38420.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

SEP 29 2009

FRONTIER OIL COMPANY
 1720 KSB&T BLDG #1 KELLER "B" 30-10-19W
 WICHITA, KS 67202 APPX SW SW SE
 CONTR RED TIGER DRILLING CO CTY ROOKS
 GEOL R. D. PARKER/J. A. ALBERTS FIELD MARCOTTE

E 2220 KB CM 9/16/80 CARD ISSUED 1/29/81 IP OIL WELL
 API 15-163-21,156 TOP 3287-95
 LKC 3498-3546 OA

+	+
+	+
+	+

SMP	TOPS	DEPTH	DATUM
ANH		1612	+ 608
BRNVLE LM		2925	- 705
TARK LM		3025	- 805
HOW		3181	- 961
TOP		3205	- 985
HEEB		3424	-1204
TOR		3440	-1228
LKC		3464	-1244
B KC		3673	-1453
CHTY CONG		3702	-1482
MARM		3725	-1505
SIMP		3757	-1537
ARB		3778	-1558
RTD		3781	-1561
NO LOG			

8-5/8" 256/170sx, 4 1/2" 3780/250sx
 DST (1) 3216-3244 (TOP)/120-30-0-0, REC 20' HOCM, 70' VSOCM, 60' WM W/SPTS 0, ISIP 689#, IFP 57-102#
 DST (2) 3320-3400 (TOP)/120-30-0-0, REC 860' SL MSW, ISIP 1117#, IFP 79-520#
 DST (3) 3418-3478 (HEEB, TOR)/60-30-0-0, REC 15' M, ISIP 667#, IFP 57-57#
 DST (4) 3474-3506 (LKC)/60-30-0-0, REC 45' M W/SCUM 0, ISIP 159#, IFP 45-68#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)

FRONTIER OIL COMPANY
 #1 KELLER "B"
 CARD #2
 30-10-19W
 APPX SW SW SE
 500 G (15% REG), SWB PT LD & REC 2-32 BF, 20% O/1HR,
 2-32 BF, 15% O/2ND HR, 1.74 BF, 15% O/3RD HR, PF (LKC)
 4/3498-3504, SET 4 1/2" PLUG @ 3522, SWB DWN & REC 2.98 BF,
 50% O, SWB 1.16 BF, 10% O, AC 500 G (15% REG), REC LD &
 SWB 4.64 BF, 20% O/1HR, 4.06 BF, 30% O/2ND HR, 2.90 BF,
 40% O/3RD HR, 2.90 BF, 40% O/4TH HR, 2.32 BF (TOP), 4/3287-95
 SET 4 1/2" PLUG @ 3468, SWB DWN & REC 2.32 BW/30", SWB 4.64
 BW/1HR, SET 2-3/8" T @ 3315, PF (TOP) 4/3234-40, TST WTR
 AC 500 G (15% REG), REC LD & SWB 4.06 BF, 40% O/1HR, 3.48
 BF, 25% O/2ND HR, SWB AVER 1.74 BFPH, 15% O/6HRS, POP,
 OIL WELL - POTENTIAL NA

FRONTIER OIL COMPANY #1 KELLER "B" 30-10-19W
 APPX SW SW SE
 DST (5) 3506-3528 (LKC)/60-30-0-0, REC 30' M, ISIP 204#, IFP 17-28#
 DST (6) 3526-3546 (LKC)/120-30-0-0, REC 120' VSOCM, ISIP 158#, IFP 22-90#
 DST (7) 3548-3606 (LKC)/60-30-0-0, REC 15' M, ISIP 509#, IFP 68-68#
 DST (8) 3604-3712 (B KC-CONG)/60-30-0-0, REC 5' M, ISIP 373#, IFP 102-102#
 DST (9) 3658-3771 (CONG, MARM)/60-30-0-0, REC 10' M, ISIP 216#, IFP 80-80#
 DST (10) 3658-3781 (CONG, MARM, SIMP)/60-30-0-0, REC 15' M, PRESSURES NA
 DST (11) 3640-3781/60-30-0-0, REC 61' M, PRESSURES NA
 MICT - CO, PF (LKC) 4/3542-46, SET 4 1/2" PLUG @ 3632, AC

(CONT)