

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21072-00-00  
Spot: NENESW Sec/Twnshp/Rge: 3-22S-24W  
2275 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: DECHANT Well #: 3-111  
County: HODGEMAN Total Vertical Depth: 4750 feet

Operator License No.: 30104  
Op Name: CAMBRON, PAUL L.  
Address: 118 N PENN PO BOX 384  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	672		WITH 450 SX CMT TO SURFACE
PROD	4.5	4747	0	WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2009 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: MOE SMITH Company: CHEYENNE WELL SERVICE Phone: (785) 798-2282

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS THEN GEL SPACER TO 1700'. CIRCULATE CMT TO SURFACE. TIED ONTO BACKSIDE & PUMP 150 SX CMT IF POSSIBLE.  
154.38

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/22/2009 12:10 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 25 SX CMT - 200# HULLS - 13 SX GEL & 110 SX CMT. MAXIMUM PRESSURE 1400#. SHUT IN PRESSURE 1000#. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4676	4690		

INVOICED

DATE 10-27-09  
INV. NO. 2010060409

RECEIVED  
OCT 01 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED

SEP 25 2009

KCC DODGE CITY