

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20397-00-01/²
Spot: NE ne Sec/Twnshp/Rge: 12-32S-42W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: HARRISON Well #: 1-12
County: MORTON Total Vertical Depth: 5302 feet

Operator License No.: 32782
Op Name: DCP MIDSTREAM, LP
Address: 370 17TH ST STE 2500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1540		WITH 4 SX CMT
CIBP		2900		WITH 5 SX CMT
CIBP		5000		WITH 4 SX CMT
SURF	8.625	1535		
COND	13.38	50		
PROD	4.5	5258	543	

172.32

Well Type: GW 65W UIC Docket No: _____ Date/Time to Plug: 09/02/2009 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: _____ Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/03/2009 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

9/2/09: CIBP @ 5000' WITH 4 SX CMT. CIBP @ 2900' WITH 5 SX CMT. TESTED 5 1/2" CASING TO 300 PSI. HELD OK. 9/3/09: RAN CMT BOND LOG FORM 1900' TO 540'. TOC @ 608'. CIBP @ 1540' WITH 4 SX CMT. PLUG AT 510' WITH 87 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5044	5050		
5039	5041		

INVOICED
DATE 10-27-09
INV. NO. 2010060431

RECEIVED
OCT 01 2009
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED

SEP 22 2009

Signed

Jack MacLachlan
(TECHNICIAN)

KCC DODGE CITY