

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02095-00-00
Spot: SENWSW Sec/Twnshp/Rge: 31-22S-11W
1660 feet from S Section Line, 990 feet from W Section Line
Lease Name: ALLEN A Well #: 3
County: STAFFORD Total Vertical Depth: 3558 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|-----------------|
| SURF | 13 | 220 | | WITH 200 SX CMT |
| PROD | 7 | 3531 | 0 | WITH 250 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2009 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 3480' & 7 SX CMT ON TOP OF SAND. PERFORATE @ 600'. RUN TBG TO 600' & CIRCULATE CMT. PULL TBG. PERFORM A LIGHT SQUEEZE ON 7".
115.64

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 09/25/2009 10:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SQUEEZED @ 45' TO 66' W/209 SX CMT. SQUEEZED @ 64' TO 94' WITH 150 SX CMT. SANDED BOTTOM TO 3170' & 7 SX CMT WITH DUMP BAILER. PERFORATED 7" @ 600'. RAN TBG TO 620'. PUMPED 135 SX CMT CIRCULATING TO SURFACE. PULLED TBG OUT OF HOLE. SQUEEZED DOWN 7" WITH 45 SX CMT. PRESSURD TO 300 PSIG & HOLDING.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3531 | 3558 | OH | |

INVOICED

DATE 10/27/09
INV. NO. 2010060434

RECEIVED
OCT 01 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
SEP 25 2009
KCC DODGE CITY