

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02097-00-00
Spot: NW NESW Sec/Twnshp/Rge: 31-22S-11W
2330 feet from S Section Line, 1660 feet from W Section Line
Lease Name: ALLEN A Well #: 5
County: STAFFORD Total Vertical Depth: 3560 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13	227		WITH 200 SX CMT
PROD	7	3532	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2009 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3480' & 7 SX CMT. RUN BOND LOG & DETERMINE PLUGGING METHOD
115.70

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 09/24/2009 9:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SQUEEZED @ 2800' TO 2900' WITH 100 SX CMT ON 9/12/50. SANDED BOTTOM TO 3480' & DUMPED 7 SX CMT WITH DUMP BAILER. BOND LOG INDICATED CMT FROM 600' TO 0' THROUGH 1". RAN TBG TO 620' & PUMPED 145 SX CMT. CIRCULATING CMT TO SURFACE. PULLED TBG & TOPPED OFF 7" WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3532	3560	OH	

INVOICED
DATE 10-27-09
INV. NO. 2010060434

RECEIVED
OCT 01 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
SEP 25 2009
KCC DODGE CITY