

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20810-00-00
Spot: NWSESW Sec/Twnshp/Rge: 4-26S-4W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: REUSSNER EAGLE Well #: 1
County: RENO Total Vertical Depth: 4275 feet

Operator License No.: 31409
Op Name: M M ENERGY, INC.
Address: PO BOX 21904
OKLAHOMA CITY, OK 73156

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4000		
SURF	8.625	317		275 SX 138.94
PROD	4.5	4270		440 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2009 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE MURPHY Company: MM ENERGY Phone: (405) 463-3355

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 09/17/2009 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

9/16/2009 CIBP SET AT 3500' BAILER USED TO PLACE 2 SXS OF CEMENT ON TOP OF CIBP. 4.5" CASING PIPE KNIFED OFF AT 2624', CASING PULLED 825' 9/17/2009 -50 SXS CEMENT (WITH 3% CC) PLUG SPOTTED AT 825', WAITED 1.5 HOURS TO TAG TOP OF CEMENT AT 650'. AT 420' CIRCULATED 200 SXS OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4099	4101	CSG	
3650	3655	CSG	

INVOICED
DATE 10-27-09
INV. NO. 2010060436

RECEIVED
SEP 29 2009
KCC WICHITA

Remarks: CEMENT COMPANY IS COPELAND OUT OF GREAT BEND, 60-40-4% POS MIX, TICKET #32930. GPS - LAT - 37.80984, LONG--97.76677

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)