

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00920-00-01

Spot: SWNESW

Sec/Twnshp/Rge: 16-10S-20W

1663 ~~1650~~ feet from S Section Line, *3650* feet from E Section Line

Lease Name: TOWNS

3606 Well #: COWGILL 1

County: ROOKS

Total Vertical Depth: 3795 feet

Operator License No.: 5259

Op Name: MAI OIL OPERATIONS, INC.

Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260	0	w/175 sxs cmt
PROD	4.5	3774	0	w/75 sxs cmt <i>123.34</i>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/28/2009 9:30 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: KENT WILLSON

Company: MAI OIL OPERATIONS, INC.

Phone: (785) 483-1683

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Packer stuck in the hole at 3400'. Tubing backed off at 2305'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/28/2009 12:00 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2300' - pumped 125 sxs 60/40 pozmix - 4% gel with 250# hulls.
Pulled tubing to 1000' - pumped 40 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked onto 4 1/2" casing - pumped 40 sxs 60/40 pozmix with 50# hulls.
S.I.P. 300#.
Checked 8 5/8" - 4 1/2" annulus. Pressured immediately.

Perfs:

RECEIVED

OCT 02 2009

KCC WICHITA

RECEIVED

OCT 02

KCC WICHITA

INVOICED

DATE 10-27-09

INV. NO. 2010060437

Remarks: ALLIED CEMENTING COMPANY-TICKET #037557.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

PKT

