

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22675-00-00
Spot: NENENENW Sec/Twnshp/Rge: 5-20S-23W
5083 feet from S Section Line, 2854 feet from E Section Line
Lease Name: STUM VERN Well #: 1
County: NESS Total Vertical Depth: 4470 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	329		WITH 225 SX CMT
PROD	4.5	4456	0	WITH 150 SX CMT

145.28

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/03/2009 1:00 PM
Plug Co. License No.: 7146 Plug Co. Name: CHEYENNE OIL SERVICES, INC.
Proposal Rcvd. from: MOE SMITH Company: CHEYENNE OIL SERVICES, INC. Phone: (785) 798-2282

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 35 SX CMT & 150# HULLS. PULL TBG TO 1500' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/03/2009 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

12/28/04: CASING WAS PERFORATED @ 1530'. PUMPED CMT & LOST CIRCULATION. RAN TEMP. SURVEY FOUND CMT @ 650#. PERFORATED @ 620'. COULDN'T PUMP IN. WENT DOWN BACKSIDE WITH 225 SX CMT. RUN TBG TO 4370' & PUMP 35 SX CMT & 150# HULLS. PULL TBG TO 1530' & PUMP 135 SX CMT. CMT CIRCULATED TO SURFACE. PULL TBG & TOP OFF WITH 35 SX CMT. TIE ONTO BACKSIDE & PRESSURED UP TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4379	4384		

INVOICED

DATE 10/27/09
INV. NO. 2010 060438

RECEIVED
OCT 01 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED
SEP 25 2009
KCC DODGE CITY