

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21635-00-00
Spot: N2N2NWSW Sec/Twnshp/Rge: 21-31S-5W
2450 feet from S Section Line, 660 feet from W Section Line
Lease Name: HELEN Well #: 1-21
County: HARPER Total Vertical Depth: 4810 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	4654		
SURF	8.625	267		200 SX <u>156.33</u>
T1	2.875	4618		
PROD	5.5	4792	3534	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (785) 483-5371

Proposed Plugging Method: SET CIBP 4585' AND 2 SKS, PULL CASING. 35 SKS 800, 35 SKS 600', CIRC CMT 310-0

Plugging Proposal Received By: B. J. HOPE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2009 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4580' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 3534', AND PULLED TO 829', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 330 WHERE CMT WAS CIRC. TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4659	4661	CSG	
4635	4638	CSG	

INVOICED
DATE 10-27-09
INV. NO. 2010060439

RECEIVED
OCT 05 2009
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

PKT