

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-22163-00-01
Spot: SWSESW Sec/Twnshp/Rge: 15-23S-10E
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BLEDSONE Well #: 2
County: GREENWOOD Total Vertical Depth: 2176 feet

Operator License No.: 33336
Op Name: ESS CORPORATION
Address: 1533 20TH PARK PL
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		101		
PROD	4.5	2176	361	

70.72

Well Type: EOR UIC Docket No: E21357.1 Date/Time to Plug: 09/01/2009 8:00 AM
Plug Co. License No.: 31789 Plug Co. Name: EASY STREET OIL, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @2100' 50' cement plug @ 900' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2009 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2100' pumped 7 sxs cement, shot casing @ 750' pumped 20 sxs cement, shot casing @ 361' pulled casing out ran tubing to 250' pumped 84 sxs cement to surface.

Perfs:

Top	Bot	Thru	Comments
2110	2130		

INVOICED
DATE 11-13-09
INV. NO. 2010060486

RECEIVED
OCT 06 2009
KCC WICHITA

RECEIVED
KCC DISTRICT #3

SEP 28 2009

MH


CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

PKA