

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00049-00-00
Spot: SWNENW Sec/Twnshp/Rge: 26-12S-16W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: FURTHMEYER Well #: 2
County: ELLIS Total Vertical Depth: 3408 feet

Operator License No.: 3956
Op Name: BRUNGARDT OIL AND LEASING INC.
Address: 529 E 14TH PO BOX 871
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	206	0	w/unknown sxs cmt
L1	4.5	1348		
PROD	7	3400	0	w/unknown sxs cmt 110.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2009 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY L. BRUNGARDT Company: BRUNGARDT OIL AND LEASING I Phone: (785) 483-4975

Proposed Plugging Method: Ordered 340 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel.
Tiger Wireline Service perf at 1800' - 1145' - 775' - 150'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2009 2:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2740'.
Allied rigged to tubing - pumped 14 sxs gel - followed with 75 sxs 60/40 pozmix with 200# hulls mixed in.
Pulled tubing to 1800' - rigged to tubing and pumped 75 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1140' - rigged to tubing and pumped 75 sxs cement to circulate cement with 100# hulls.
Pulled tubing - rigged to 4 1/2" casing and pumped 25 sxs cement to circulate cement out 7" casing.
Shut in 7" and pumped 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Rigged to 10 3/4" casing and pumped 40 sxs cement.
Max. P.S.I. 200# S.I.P. 200#.

Perfs:

RECEIVED
OCT 09 2009
KCC WICHITA

INVOICED
DATE 11-13-09
INV. NO. 2010060483

Remarks: ALLIED CEMENTING COMPANY-TICKET #037652.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

OCT 07 2009

[Handwritten initials]

KEWANEE OIL CO.

2

FURTHMEYER

26-12-16W
SW NE NW 34

Contr. GROSS DRILLING CO.

ELLIS

County

E. 1922

Comm

Comp. 9-12-52

IP 80 BOPD

Tops	Depth	Datum
LANS	3130	-1208
ARB	3101	-1179
T D	3108	-1186

Casing
7" 3402 ACID 3500

EMMERAM N.E. POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS