

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20468-00-00
Spot: NENWNENW Sec/Twnshp/Rge: 22-34S-21W
4989 feet from S Section Line, 3473 feet from E Section Line
Lease Name: BARBY-HARPER Well #: 3-22
County: CLARK Total Vertical Depth: 5160 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4230		WITH 2 SX CMT
SURF	8.625	854		WITH 450 SX CMT
COND	20	115		WITH 400 SX CMT
PROD	4.5	5159	2150	WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2009 9:50 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: DAVID PAULY Company: C.H. TODD Phone: (316) 264-7566

Proposed Plugging Method: CIBP @ 4230' & 2 SX CMT. PLUG AT 870' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2009 10:25 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 4230' WITH 2 SX CMT. 1ST PLUG AT 882' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5068	5078		
4285	4295		
4279	4283		

RECEIVED
OCT 08 2009
KCC WICHITA

INVOICED

DATE 11-13-09

INV. NO. 2010060484

Remarks: USED 60/40 POZMIX 4% GEL BY QULAIITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED

OCT - 2 2009

KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-23
[Signature]