

15-051-22900-00-00

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15- 051-22,900 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Murchison Oil & Gas

Complete Address 2500 Diamon Shamrock Tower, 717717 No. Harwood, Dallas, Texas

Lease Name McIntosh Well No. #1

Location SE SW SW Sec. 6 Twp. 12 Rge. 18 (East) (West)

County Ellis Total Depth 3676'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Big Springs Drilling, Inc.

Address Box 8287 Munger Station, 400 N. Woodlawn, Wichita, License No. _____
Kansas 67208

Operation Completed: Hour: 8:45PM Day: 23rd Month: March Year: 1982

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

8 5/8"-261' s.p. cuc. w/165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of bulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

Amount of Surface Casing: 261' of 8 5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 3-30-82

INV. NO. 9795-W

RECEIVED
STATE CORPORATION COMMISSION
3-29-1982
MAR 29 1982

CONSERVATION DIVISION
WICHITA, KANSAS