

15-051-20088-00-00

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

5-5-1976
MAY 05 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Woodman-Iannitti Drilling Company

Complete Address Box 308, Great Bend, Kansas 67530

Lease Name Stackhouse Well No. 3

Location G S/2 NE NW Sec. 7 Twp. 12 Rge. (E) (W) 18

County Ellis Total Depth 3745'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 11:30 A Day 4 Month 5 Year 1976

The above well was plugged as follows:

Total Depth 3745' 8 5/8 csg set 185' cwc 145 sk.

5 1/2 csg set 3742' cw 125 sk cem.

5 1/2 csg PBD 3715' with perf. (3417')

Set 5 1/2 wood plug at 3350' -poured 10' sd -dumped 4 sk cem W/dump bailer. (3350-3300)

Cutoff & recovered 2840' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs

hulls- 70 sk cem. -8 sk gel & water -released 8 5/8 plug & 50 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Res Massery
Well Plugging Supervisor

DATE 5/5/76

INV. NO. 3168-W