

15-051-30436-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-5-1976
MAY 05 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION
Wichita (of this well)

Operator's Full Name Woodman-Iannitti Drilling Company

Complete Address Box 308, Great Bend, Kansas 67530

Lease Name Stackhouse Well No. 1

Location N/2 SE NW Sec. 7 Twp. 12 Rge. (E) (W) 18

County Ellis Total Depth 3747'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 1 P Day 4 Month 5 Year 1976

The above well was plugged as follows:

Total Depth 3747' 8 5/8 csg set 171' cwc 135 sk.

5 1/2 csg set 3744' cw 150 sk cem.

5 1/2 csg FBTD 3732' with top perf. (3446')

Ser 5 1/2 wood plug at 3400' -poured 10' sd -dumped 4 sk cem W/dump bailer. (3400-3350)

Shutoff & recovered 2205' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs

hulls -70 sk cem. -8 sk gel & water -released 8 5/8 plug & 50 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 5/5/76

INV. NO. 3167-W