

15-051-20209-00-00  
KANSAS  
STATE CORPORATION COMMISSION

Form CP-3  
Rev. 6-26-62

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
2-26-1968  
FEB 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Woodman-Iannitti

Complete Address: 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Johnson Well No. 2

Location NW SW NE Sec. 7 Twp. 12 Rge. 18 (E)    (W) X

County Ellis Total Depth 3790'

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor:    Co. Tools   

Address:    License No.   

Operation Completed: Hour 11:15 A Day 24 Month 2 Year 1968

The Above well was plugged as follows:

RTD 3790 8 5/8 csg set at 178' cwc 150 sc. Cem. Mat. 100 sc 50-50 poz cem. W/6% gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cement  
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 2/26/68  
7314-W

Signed: Geo F. Messer  
Well Plugging Supervisor