

KANSAS

FORM CP-3
Rev. 5-5-81

15-051-22440-00-00
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 051-22,440 ✓

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name SEVILLE ENERGY CORPORATION

Complete Address 3022 EXPRESSWAY # 213 OKLAHOMA CITY, OKLAHOMA

Lease Name STACKHOUSE Well No. #1

Location NE-NE-NW Sec. 7 Twp. 12 Rge. 18 (East) (West)

County ELLIS Total Depth 3742 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor BUFFALO DRILLING COMPANY, INC.

Address 435 PAGE COURT. BROADWAY & DOUGLAS WICHITA, MO. License No. _____

Operation Completed: Hour: 10:00 PM Day: 16th Month: JUNE Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" 306^{ET} S. CUL w/ 175ST 60/40 PREMIX - 2% GEL. 3% CA-CL.
ORDERED 110ST 50/50 PREMIX 6% GEL. + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG @ 800^{ET} w/ 65ST CNT.
2ND PLUG @ 330 w/ 30ST CNT.
3RD PLUG - SOLID BRIDGE @ 40^{ET} w/ 10ST CNT.
5TH IN RHT GOLF.
CEMENTED BY ALLIED CNT.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
6-18-1981
JUN 18 1981

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 7-27-81

INV. NO. 5994-W

CONSERVATION DIVISION
Wichita, Kansas