

15-051-21675-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 21,675 (of this well)

Operator's Full Name Raymond Oil Co., Inc.

Complete Address 200 W. Douglas, Wichita, Ks.

Lease Name Stackhouse Well No. 1

Location SW NE SW Sec. 7 Twp. 12 Rge. (E) (W) 18

County Ellis Total Depth 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Ks. License No.

Operation Completed: Hour 2:45 P Day 23 Month 4 Year 1979

The above well was plugged as follows:

RTD 3740 10 3/4 csg set 217' cwc Plg. Mat. 50-50 poz 4% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 210' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1979
4-26-1979

CONSERVATION DIVISION

I hereby certify that the above well was plugged as herein stated, Wichita, Kansas

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-27-79
INV. NO. 95150W