

15-051-00651-00-00
DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 29-32

LOCATION NW NW NE

SEC. 9 TWP. 12 RGE. 18

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Holy Cross

Operator Aylward Drg Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3691 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 126' circulated with cement - 5 1/2" at 3682' with 100
sax cement behind.

Filled with chat to 3670', set 4 sax cement with dump bailer,

pulled 3100' 5 1/2", filled hole with mud to 150', set plug

and 15 sax cement, filled with mud to 40', set rock bridge and

10 sax cement to bottom cellar.

PLUGGING
DATE 9-18-51
PAGE 129 OF 32

J. P. [Signature]
District Conservation Agent
Date 12-20-51
RECEIVED
12-26-1951
DEC 26 1951