

15-051-21088-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
9-23-1975
SEP 23 1975

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name F & M Oil Co., Inc.

Complete Address 603 505 Union Center, Wichita, Kansas

Lease Name Schmeidker Well No. 1

Location SW NW NE Sec. 9 Twp. 12 Rge. (E) (W) 18

County Ellis Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 2 A Day 22 Month 9 Year 1975

The above well was plugged as follows:

RTD 3720' 8 5/8 csg set 206' c2c 150 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Wessley
Well Plugging Supervisor

DATE 9-26-75

INV. NO. 1976-W