

15-051-20038-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

4-7-1967
APR 7 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Dreiling & Jennings

Complete Address: Victoria, Kansas R.R. #2

Lease Name Baker Well No. 2

Location SW NW SE Sec. 10 Twp. 12 Rge. 18 (E) (W) X

County Ellis Total Depth 3605

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons

Address: Victoria, Kansas License No.

Operation Completed: Hour 1:30 P Day 5 Month 4 Year 1967

The Above well was plugged as follows:

RTD 3605' 8 5/8 csg set at 134' cwc 100 sc.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 20 sc cem.

thru drill pipe, Heavy mud to 125' set cementing plug, and displaced 20 sc cement thru

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to

base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Prof. Massey
Well Plugging Supervisor

DATE 4/7/67

INV. NO. 5016-W