

15-051-04343-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
1-15-1964
JAN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty
Complete Address: 800 Bitting Bldg Wichita, Kans
Lease Name Baker Well No. 1
Location SW SW SE Sec. 10 Twp. 12 Rge. (E) (W) 18
County Ellis Total Depth 3750
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Glenn & Smith
Address: Ellinwood, Kans License No. 396
Operation Completed: Hour 6PM Day 10 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3737' with 75 sax cement.

Sand back to 3720', set 4 sax cement with dump bailer - pulled 3300'
5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550'
(30 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to
190', displaced 20 sax cement through 5 1/2" at 190', heavy mud to 55'
cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Petty*
Well Plugging Supervisor

DATE 1/15/64
INV. NO. 8463-w