

15-051-04187-00-00  
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 13-39

LOCATION NW SE SE

SEC. 10 TWP. 12 RGE. 18

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. D-1 Lease Baker

Operator Petroleum Inc Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3705 Feet.

Plugging Contractor Morgan Well Pulling

Plugging Contractor's License No. 43

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 194' circulated with cement - 5 1/2" at 3700' with 50 sax cement behind.

Filled with chat to 3695' set 4 sax cement with dump bailer, pulled 3200' 5 1/2", mudded hole to 194', set rock and 15 sax cement, top cement at 150'.

Left as water well for land owner as per attached.

RECEIVED  
STATE CORPORATION COMMISSION  
**PLUGGING**  
FILE SEC 10 T 12 R 18 W 36-1954  
BOOK PAGE 13 LINE 39  
WICHITA, KANSAS

Eldon Lee  
District Conservation Agent  
Date 5-5-54