

15-051-04834-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 10-26

LOCATION NE NE NE

SEC. 10 TWP. 12 RGE. 18

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Baker

Operator Graham Oil Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3667 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3650'
with 100 sax behind.

Filled with chat to 3640' set 4 sax cement with dump bailer,
pulled 690' 5 1/2", filled with hravy mud to 160', set wood
plug, rock bridge and 15 sax cement, filled with heavy
mud to 35', set bridge and 10 sax cement to bottom cellar.

RECEIVED
Conservation Div.
8-7-1950
AUG 7 - 1950

STATE CORPORATION
COMMISSION

Leon Kelly
District Conservation Agent

Date 8-4-50

PLUGGING
SEC. 10 TWP. 12 RGE. 18
AUG 10 1950